

OFFICIAL NOTICE TO CONTRACTORS

Notice is hereby given that sealed bids will be received up to **10:00 a.m., Friday, June 1, 2018**, in the Office of Director of Public Works, Municipal Building, 75 North Bonson Street, Platteville, WI 53818 for the following work, at which time and place all bids shall be publicly opened and read.

Contract 6-18 SIDEWALK REPAIR

All bids shall be addressed to the Director of Public Works, Municipal Building, 75 North Bonson Street, Platteville, WI 53818, with the name and address of the bidder, contract number and title of work distinctly indicated on the outside of the envelope.

Contract documents together with plans and specifications for this project are on file for examination and may be obtained in the office of Director of Public Works, on the City of Platteville website (platteville.org), or via e-mail by contacting sigwarthd@platteville.org.

Sealed bids must be accompanied by a certified check or bid bond payable to the City of Platteville, Wisconsin in the amount of not less than five (5) percent of the total amount of bid as a guarantee that if the bid is accepted, bidder will execute and file proper contract documents, performance bond and insurance within ten (10) days after award of the contract.

When the intended awardee so executes the contract agreement and files bonds and insurance as required by the contract documents, the check or bid bond will be returned.

In case the intended awardee fails to execute the contract agreement and file bonds and insurance as required by the contract documents, the amount of the check or bid bond submitted with the contractor's proposal shall be forfeited as liquidated damages.

All bids shall be made on the proposal forms furnished in the contract documents. Any alteration or extension of the form or the furnishing on it of unsolicited information may cause the bid to be declared informal and result in its being rejected.

No bid shall be withdrawn for a period of thirty (30) days after the scheduled time of opening bids.

The City reserves the right to reject any or all bids, to waive any informalities in bidding, or accept the bid deemed most advantageous to the City.

Karen Kurt
City Manager

Publish Dates: Shopping News: May 15 & 22, 2018
 Platteville Journal: May 16 & 23, 2018

BIDDER'S PROPOSAL

FOR: Sidewalk Repair
Contract #6-18

BID OPENING: Friday, June 1, 2018 10:00 AM

TO: Office of the Director of Public Works, City of Platteville, Platteville, WI

The undersigned hereby proposes to furnish all labor, tools, equipment, and appliances and all materials, except as definitely specified to be furnished by others, and construct advertisement, plans, specifications, and contract, all as attached hereto and all of which the undersigned has examined, the following work for the compensation indicated:

QTY & ITEM	UNIT PRICE	TOTAL COST
1) Removing Concrete Sidewalk 313.67 SY		
_____ \$/SY (Written unit cost)	\$ _____ SY (Numerical)	\$ _____
2) Remove Cub & Gutter 10 LF		
_____ \$/LF	\$ _____ LF	\$ _____
3) New 4" Sidewalk 1558 SF		
_____ \$/SF	\$ _____ SF	\$ _____
4) New 6" Sidewalk 1265 SF		
_____ \$/SF	\$ _____ SF	\$ _____
5) New 24" Curb & Gutter 10 LF		
_____ \$/LF	\$ _____ LF	\$ _____
6) Install Detectable Plates 1 EA		
_____ \$/EA	\$ _____ EA	\$ _____
TOTAL BASE BID	\$ _____	

I have completed and attached the Bidder's Proposal, the Proposal Guaranty (bond or certified check), Affidavit of Organization and Authority, and List of Subcontractors.

**SPECIAL PROVISIONS
CONTRACT 6-18
SIDEWALK REPAIR**

SCOPE OF WORK: This project consists of removing and replacing damaged sidewalks and curb and gutter, constructing pedestrian ramps and such other miscellaneous work as may be called for on the plans or in the specifications.

LOCATION OF THE WORK: The work is in various locations as listed or shown on the attached tabulations and location maps.

FORMING OF CURB AND GUTTER: The curb and gutter is to be formed on the flag line and the back of curb. The forms shall be of a uniform surface, such as, to create a smooth, even and uniform vertical wall on the curb. **All cutting and grinding of sidewalk adjacent to commercial properties will have dust control procedures during the grinding and cutting operations.**

Contractor to cut slope of trip hazard on sidewalk at 4-1 minimum.

DETECTABLE PLATES: The item shall be a 2 foot by 4 foot panel impressed into the wet concrete according to manufacturer's instructions. The only acceptable manufacturers are those approved by Wisconsin DOT. The Contractor shall identify those ramps that cannot accept a 4 foot wide panel and at the Engineer's sole discretion, the Contractor shall install a 2 foot by 2 foot or 2 foot by 3 foot panel by the same manufacturer, under the same bid item. See Sidewalk and Curb & Gutter Specifications, 3.16.

STRUCTURES IN CONCRETE SIDEWALK: All structures in concrete sidewalk, i.e. curb-stops and power poles, will have expansion joint material wrapped around it, flush with top of sidewalk.

SURFACE RESTORATION: All excavation debris will be removed from the job site at the time of construction. All fill material will be shredded soil with no debris in soil.

AMOUNT OF WORK: The City of Platteville reserves the right to add or delete work from the project to meet budgetary goals. The addition or deletion of work may result in a change in the quantities as bid. Should the City add or delete work which is substantially different from the quantity bid, the payment for such work will be negotiated according to the General Conditions.

TIME OF COMPLETION AND LIQUIDATED DAMAGES: The City work shall be completed within 90 calendar days from the start date identified on the notice to proceed. The contractor agrees that the City may deduct from monies due the contractor the sum of **two hundred (\$200.00) dollars per day as liquidated damages**, for each working day beyond the date of completion that the contract remains uncompleted.

WORKING DAY: Working days are defined as Monday through Friday (excluding national holidays), between the hours of 7:00 a.m. and 5:00 p.m. Days during which weather conditions prohibit work will not be classed as working days. Working days will be computed in 1/2 day increments. The Director of Public Works is the sole judge of conditions which prohibit work.

COMPLETION: Completion means that all work, including surface restoration, and clean up has been accomplished. It also includes seeding and mulching; however, touch up seeding and mulching may also be done in the spring, weather dependent. The retainage shall be adjusted to reflect in a proportionate manner the seeding & mulching carried over till spring.

INSURANCE: Contractor shall provide certificate of insurance for the following required coverage.

1. Comprehensive General Liability Insurance - with bodily injury coverage of not less than \$1,000,000 each person and \$1,000,000 each accident and property damage coverage of not less than \$1,000,000. Comprehensive General Liability to include premises and operations. Contractor's protective liability, products liability including completed operations coverage and contractual liability.
2. Personal Injury - false arrest, detention or imprisonment or malicious prosecution, libel, slander, defamation or violation of right of privacy, wrongful entry or eviction or other invasion of right of private occupancy to be included.
3. Comprehensive Automobile Liability Insurance - with bodily injury coverage of not less than \$500,000 each person and \$1,000,000 each accident and property damage coverage of not less than \$500,000. Comprehensive Automobile Comprehensive Automobile Liability to include all owned and non-owned automobiles.
4. In lieu of the above limits, a single limit policy in the amount of \$2,000,000 or a \$2,000,000 Umbrella is accepted.
5. Bodily Injury Protection - under both comprehensive general and comprehensive automobile forms shall be on an "occurrence" basis.

Contract 6-18A

Contractor to provide dust control to eliminate most of the dust from the grinding of the trip hazard at the grinding site.

**CITY OF PLATTEVILLE
CONTRACT 6-18A**

BIDDER'S PROPOSAL

FOR: Contract 6-18A SIDEWALK GRINDING OF TRIP HAZARDS

:

QTY & ITEM	UNIT PRICE	TOTAL COST
------------	------------	------------

- 1) Grinding of city sidewalks (80 Grinds)
Average total inch/foot in the last 4 years is 2.0 inch/foot per grind

_____ per grind (Written unit cost)	\$_____ per grind (Numerical)	\$_____
--	----------------------------------	---------

Contract 6-18A	TOTAL	\$_____
-----------------------	--------------	----------------

Contractor to cut slope of trip hazard on sidewalk at 4-1 maximum.

Contractor to describe dust control procedures during grinding operations.

Bid Schedule Summary

Contract #6-18 Replacement Of City Sidewalks

Contract #6-18 Total = \$_____

Contract #6-18A Grinding of City Trip Hazards

Contract # 6-18A Total = \$_____

Contract Total = \$_____

CITY OF PLATTEVILLE

2018 SIDEWALK REPAIR LOCATIONS

Southwest Rd.	Jay St. – S. Chestnut St. (N. Side)
Southwest Rd.	Markee Ave – S. Court St. (S. Side)
Division St.	S. Hickory St. – S. Chestnut St. (N. & S. Side)
Bradford St.	Irene St. – W. Pine St. (W. & E. Side)
N. Elm St.	Furnace St. – Adams St. (W. & E. Side)
Park Pl.	Furnace St. – Cedar St. (E. Side)
Jefferson St.	E. Cedar St. – E. Madison St. (W. & E. Side)
Second St.	Herman St. – Sylvia St. (W. & E. Side)

2018 Grinding of sidewalks As of 5/2/18

Southwest Rd. @ Jay North Side

560 4 Grnds
520 1 Grnd
460 2 Grnds
380 1 Grnd
340 1 Grnd
280 1 Grnd

Southwest Rd. @ Markee South Side

600 1 Grnd
535 1 Grnd
515 1 Grnd
West Curb 1 Grnd

475 2 Grnds
465 1 Grnd
435 1 Grnd
395 1 Grnd
335 3 Grnd
350 S. Chest. 2 Grnds
340 S. Chest. 1 Grnd
195 3 Grnds

Bradford @ Pine

~~110 2 Grnds~~
~~160 3 Grnds~~

Bradford @ Irene

285 2 Grnds
385 Divis. 2 Grnds
205 2 Grnds
195 1 Grnd
~~405 Pine 2 Grnds~~

Division @ Hickory

250 2 Grnds
375 1 Grnd

Jefferson @ Dewey

280 E. Dewey 1 Grnd
640 1 Grnd
650 1 Grnd
670 1 Grnd
720 1 Grnd

Jefferson @ Cedar

355 1 Grnd
425 2 Grnd
445 1 Grnd

Elm @ Furnace

Curb @ Cedar W. 1 Grnd E. 1 Grnds
260 1 Grnd
360 2 Grnds
235 2 Grnds 275 1 Grnd
215 1 Grnd

Park Place @ Furnace

215 1 Grnd

2nd @ Herman

830 1 Grnd
850 1 Grnd
900 1 Grnd
960 1 Grnd
969 2 Grnds

2nd @ Pitt

1090 2 Grnd Curb 1 Grnd
Curb N. 1 Grnd S. 1 Grnd
1045 1 Grnd
1025 2 Grnd
945 3 Grnd
925 1 Grnd
905 3 Grnd
855 1 Grnd
825 1 Grnd

2018 Replacement of sidewalks

As of 5/2/18

Southwest Rd. @ S. Hickory—S. Chest. North Side

460 2 areas
420 2 areas
400 4 areas
380 1 area
220 1 area
330 S. Chest 1 area

Southwest Rd. @ Markee- S.Court South Side

625 1 area
605 1 area
585 2 area
565 2 area
535 4 areas
435 1 area
395 1 area
365 1 area
335 4 area
350 S. Chest. 1 area

Bradford @ Irene – W. Pine

295 1 area
380 Divis. 1 area

Division @ S. Hickory – S. Chest

225 1 area
445 2 areas
360 1 area

Jefferson @ Cedar – E. Lewis E. Side

210 3 areas
355 1 area
405 3 areas
425 1 area
445 1 area
465 6 areas

Jefferson @ Cedar – Lewis W Side

315 E Lewis 1 Area
400 2 areas
420 1 area
430 2 areas

Jefferson @ E. Dewey – E. Madison w. Side

280 E. Dewey 1 area
640 3 areas
690 1 area

Elm @ Furnace – Adams

200 2 areas
260 1 area
360 1 areas
355 1 area
260 Cedar 2 areas
285 1 area
265 3 areas

Park Pl. @ Furnace--Cedar

215 1 area
265 3 areas

2nd @ Herman - Sylvia

830 2 areas
850 1 areas
855 1 area
900 1 area
920 3 areas
960 2 areas
969 2 areas
995 1 area
1010 3 areas
1050 1 area